

ENGINEERING DEPARTMENT.**KOLAR DIVISION.**

Abstract Notification dated 12th July 1932.

The attention of the public is invited to Page 771 and 772, Part VI of the *Mysore Gazette*, dated 21st July 1932, calling for tenders for the work of restoring Yedahalli Sadankere Regd No. 64-716 of Kolar Taluk.

The last date fixed for the receipt of the tender is 10th August 1932 at 2 P.M.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

SUBJECT.—Restoring Upparikanahalli breached tank Regd. No. 13 of Chicknaikanahalli Taluk.

Attention of the public is drawn to Notification calling for tenders for the above work in page 759 and 760, Part VI of *Mysore Gazette*, dated 21st July 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 19th August 1932.

3. An earnest money of Rs. 200 should accompany the tender.

A. TANDONI RAO,
Executive Engineer.

ARASALU-ANANDAPURAM RAILWAY CONSTRUCTION DIVISION.

Notification dated 21st July 1932.

Sealed tenders are invited from contractors who are willing to undertake construction of the following buildings at Anandapuram on Arasalu-Anandapuram Railway.

2. Tenders should be submitted in special forms which can be obtained from the Assistant Engineer-in-charge, Arasalu-Anandapuram Railway Construction Division, Shimoga, on payment of Rs. 2 which amount is not refundable under any circumstances.

3. Tenders should be addressed to the Assistant Engineer-in-charge, Arasalu-Anandapuram Railway Construction Division, Shimoga, and should reach him not later than 12 Noon on 13th August 1932, in sealed covers superscribed, "Tender for construction of buildings at Anandapuram."

4. Tenders may be for one or all the buildings specified below.

5. No tender will be considered which is not in the prescribed form.

6. Rates should be noted both in figures and in words. Tenders which quote rates as "Estimate Rates" or some per cent more or less, will not be considered.

7. The work tendered should be completed in all respects by 31st December 1932.

8. The name of the accepted tenderer will be posted on the Notice Board of the Assistant Engineer's Office, Shimoga, soon after the approval by the Superintendent, Way and Works, Mysore Railways, Mysore, and no enquiries regarding the acceptance or rejection of tenders, will be replied.

9. The final acceptance of the tender, will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject without assigning any reason therefor, any or all the tenders or any portion of any one tender.

10. Every tender should be accompanied by an earnest money of Rs. 250 which can be paid either to the Assistant Engineer-in-charge Shimoga, along with the tender, or paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender. Such of the tenderers, that pay the amount to the Auditor, should advise him that the amount is paid on account of tender for "Constructing buildings at Anandapuram."

11. The earnest money of unsuccessful tenderers will be returned as soon as the tenders are disposed of.

12. The earnest money of successful tenderers will be accepted as part payment towards deposit due by them as per para 15 below.

13. Tenders which are not accompanied with the earnest money specified in para 10 *supra*, will not be considered.

14. Successful tenderers should execute within eight days from the date of notification of acceptance of tenders, the usual railway schedule contract bond. Failure to comply with this condition, will render the tenderer liable for forfeiture of the earnest money.

15. Successful tenderers should deposit with the Assistant Engineer-in-charge, Shimoga, before they sign the schedule agreement, 5 per cent of the value of work given out to them, such sum not to exceed Rs. 500.

16. Work should be started within 15 days from the date of acceptance of tenders and the stipulated monthly progress should be kept up.

17. The time limit specified in para 7 above should be strictly adhered to and any violation of this, will render the contractor liable to forfeit his deposit not as a penalty or penalties but as ascertained and liquidated damages recovered accordingly.

18. Plans, specifications and other details of works to be done are available for inspection in the Assistant Engineer's Office, Shimoga, where intending contractors may call and obtain any information during office hours.

19. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, will be final and legally binding.

Schedule of approximate quantities of work to be done for constructing Station Building and Loco Running Rooms at Anandapuram.

Sl. No.	Particulars	Unit	Approximate quantities	
			Station building	Running Rooms
1	Earthwork excavation and filling in ...	1000 C. ft.	2,200	1,400
2	Concrete in sand mortar ...	100 C. ft.	700	300
3	Laterite stone in mortar founds and basement	100 „	1,500	1,230
4	Do arch work...	100 „	200	81
5	Do size stone in mud ..	100 „	4,300	2,060
6	Teak-wood doors with panelled shutters complete.	S. ft.	142	...
7	Teak-wood doors with battened shutters complete.	„	...	224
8	Teak-wood windows with panelled shutters complete.	„	49	...
9	Teak-wood windows with battened shutters complete.	„	...	80
10	Teak-wood windows with glazed shutters inside and panelled shutters outside, complete.	„	27	...
11	Teak-wood rectangular ventilators with glazed shutters, iron bars, etc., complete.	„	6	12
12	Teak-wood ticket window complete as per approved drawing.	No.	1	...
13	Providing shelves with 1½" thick planks on teak-wood pegs.	S. ft.	36	...
14	Teak-wood king post trusses complete including hoisting and fixing.	Each	1	...
15	Teak-wood wrought and put up including wood oiling.	C. ft.	80	60
16	Roofing with 1st class Mangalore tiles on 2"x1" teak reapers, with chunam borders complete.	100 S. ft.	2,500	1,700
17	Fixing ridge tiles set in mortar and cement pointing.	R. ft.	56	82
18	Flooring with 1½" thick Cuddapah slabs on 3" concrete and cement pointing.	100 S. ft.	1,800	...
19	Flooring with cement concrete 6" thick and plastering over with cement.	100 C. ft.	...	1,000
20	Chunam plastering ...	100 S. ft.	3,400	2,000
21	White washing two coats ...	100 „	3,400	2,000
22	Cement pointing ...	100 „	3,400	1,700
23	Silicate chocolate painting two coats ...	100 „	600	600
24	Hoisting and fixing 4½ lbs. sec. rails	R. ft.	..	43
25	Providing and fixing teak-wood railing in front of ticket window 3 ft. high and 4 ft. long.	No.	1	...
26	Supplying and fixing burnt stone slabs 6" thick one line dressed.	S. ft.	169	...

NOTE.—Roofing and Ridge tiles, Cuddapah slabs, and cement required for the above works will be delivered at Arasalu Railway Station free of cost.

D. V. NARASIMHA RAO,
Assistant Engineer-in-charge,
Arasalu-Anundapuram Railway.

MYSORE RAILWAYS.

Notification dated 19th July 1932.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 2 P.M., on 8th August 1932, for constructing a new station building in Hole-Narsipur Town Station Yard on Mysore-Arsikere Railway.

An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The work should be completed by the end of May 1933 showing monthly progress as noted in the tender.

2. Detailed estimates and plans and conditions of schedule agreement, may be seen at the Executive Engineer's Office, Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of one rupee.

4. Every tender must be accompanied by a deposit of Rs 100 in cash as earnest money and should be superscribed "Tenders for constructing a New Station Building in Hole-Narsipur Town Station Yard on Mysore-Arsikere Railway," in default of which tenders will be rejected.

5. The earnest money on rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender, it would be held as a part of security under clause 4 of the Schedule Agreement referred to.

6. The final acceptance of any tender will rest with the Superintendent, Way and Works, Mysore Railways, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the contractor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful tenderer is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled and the earnest money is forfeited to Government.

9. Definite rates against each item of work in the Schedule should be noted both in figures and in words.

10. In case the accepted tenderer quarries stone, earth, kankar, sand etc., from Railway, Government or Forest land for use on this work, Royalty at the rates fixed by the Government will be recovered from his bills.

11. The whole of the work specified in the agreement to be completed as specified in para 1 above, failing which or failing to carry out any of the conditions of the agreement, the whole of the money held in deposit or so much of it as the Agent considers proper will without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any items of work or specification, the decision of the Superintendent, Way and Works, shall be final.

Schedule.

Items of work	Unit	Quantity
<i>Station Building.</i>		
1. Earthwork excavating foundation refilling in basement with spoil (gravel).	1,000 C.ft.	2,714
2. Concrete broken stone jelly in sand mortar	100 C.ft.	1,553
3. Foundations masonry, size stone in sand mortar	"	792
4. Superstructure—burnt brick in mortar including all charges	"	4,503
5. Do arch work	"	184
6. Providing and fixing burnt stone slabs 6" thick, one line dressed	S.ft.	319
7. Plastering with chunam mortar	Sqr.	61.0
8. White washing, 2 coats	"	61.0
9. Fixing C. I. gate way for 3rd class waiting room supplied departmentally, size 7' x 5½'	No.	1
10. Do C. I. hand railings do	"	1
11. Supplying and fixing brackets of angle iron with the rod for verandah as per design supplied.	"	6
12. Teakwood panelled doors with frames and shutters 1½" thick including all fittings such as bolts, hinges, etc., complete as per specification.	S.ft.	49
13. Teakwood battened doors with frames and shutters 1½" thick including all fittings such as bolts, hinges, etc., as per specification.	"	73
14. Teakwood windows with iron bars ¾" dia., full glazed shutters inside including all fittings such as bolts, hinges, clamps, hooks, etc., complete as per specification.	"	29.5

Items of work	Unit	Quantity
15. T. W. windows with iron bars $\frac{3}{4}$ " dia. panelled shutters outside including all iron fittings, etc., as per specification.	S. ft.	54
16. T. W. Ticket window with fittings, etc., complete as per approved design.	"	16
17. Supplying T. W. barrier with turned legs in front of ticket window in III class waiting shed and fixing complete as per plan and specification.	"	21
18. Handling and fixing charges for rails 50 lbs. and $41\frac{1}{2}$ lbs. sections supplied departmentally.	R. ft.	177
19. Teakwood shelves (wall almirahs) with panelled shutters	S. ft.	24
20. Fixing wall rack with T. W. plank $1\frac{1}{4}$ " thick with brackets 2" sq. including fixing, etc., complete as per specification.	"	143
21. First Class teakwood wrought and put up including wood oiling 2 coats.	C. ft.	93.4
22. Roofing with 1st class Mangalore tiles (Yelahanka tiles) on teakwood reepers $2" \times 1"$ wood oiled—2 coats including teakwood wind ties fixed with $2\frac{1}{2}"$ screws with extra reepers, chunam borders, etc., complete. Railway material certificate will be issued for tiles from Yelahanka to Hole-Narsipur.	Sq.	28.3
23. Providing and fixing ridge tiles (Mangalore pattern) in mortar and cement pointed.	R. ft.	59
24. Flooring with Cuddapah slabs $1\frac{1}{2}"$ thick over 3" concrete broken stone jelly in sand mortar including cement pointing, etc., complete. Railway materials certificate will be issued for cuddapah slabs from Yerraguntla or Bethamcherla to Hole-Narsipur.	Sq.	16.0
25. Teakwood eave boards, $9' \times 3\frac{3}{4}"$ including painting as per approved design.	R. ft.	214
26. Teakwood finials large do	each	2
27. Teakwood pendants do	"	4
28. Silicate silver grey painting to doors and windows—2 coats—	Sq.	6.17
29. Providing cement boards on walls with borders 2" thick all round—size $5' \times 4'$ as shown.	each	4
30. Teakwood benches 6' feet long $1\frac{1}{2}$ ft. wide with strong legs and planks of $1\frac{1}{2}"$ thick well polished complete.	"	2
31. Earthwork clearing site and levelling ground	1,000 C. ft.	51,000
<i>Approach Road.</i>		
1. Earthwork for forming the road	1,000 C. ft.	2,400
2. Collecting and stacking broken stone road metal	100 C. ft.	816
3. Do Do gravel	"	408
4. Spreading and consolidating metal	"	816
5. Do Do gravel	"	408
6. Sanding and watering	L. S.	
<i>Deviation of Channel.</i>		
1. Earthwork excavation and filling the old channel with spoil (gravelly soil).	1,000 C. ft.	...
2. Fixing C. I. pipe 12" dia. across platform pipe supplied departmentally.	R. ft.	84

HASSAN DIVISION (OPEN LINES).

Abstract Notification dated 15th July 1932.

The attention of the public is invited to the detailed notifications, dated 11th July 1932 and 14th July 1932 calling for tenders for the:—

- (1) Raising of cushion over certain arched bridges on the Birur-Shimoga Railway.
- (2) Improvements to the traffic quarters on the Tarikere-Narasimharajapura Tramway.

Published on pages 736-739 of the *Mysore Gazette*, dated 14th July 1932.
The last date of submitting the tenders is 1st August 1932, in both cases.

Notification, dated 19th July 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 2 P.M., on 22nd August 1932, for collecting and spreading broken stone ballast on Mysore-Arsikere Railway.

An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The work should be completed by the end of May 1933, showing continuous equal monthly progress under collection work.

2. Details of work and conditions of schedule agreement, may be seen at the Executive Engineer's Office, Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of one rupee.

4. Every tender must be accompanied by a deposit of Rs. 100 in cash as earnest money and should be superscribed "*Tenders for collecting and spreading broken stone ballast on the Mysore-Arsikere Railway,*" in default of which tenders will be rejected.

5. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender it would be held as a part of security under clause 4 of the Schedule Agreement referred to.

6. The final acceptance of any tender will rest with the Superintendent, Way and Works, Mysore Railways, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the contractor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled, and the earnest money will be forfeited to Government.

9. Definite rates against each item of work in the schedule should be noted both in figures and in words. Tenders may be sent up for all or a few of the sections noted in the schedule.

10. In case the accepted tenderer quarries, ballast, etc., from Railway, Government or Forest land for use on this work, Royalty at the rates fixed by the Government will be recovered from his bills.

11. The whole of the work specified in the agreement to be completed as specified in para 1 above, failing which or failing to carry out any of the conditions of the agreement, the whole of the money held in deposit or so much of it as the Agent considers proper will, without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any items of work or specification, the decision of the Superintendent, Way and Works, shall be final.

Schedule.

	Items of work	Unit	Quantity
1	Collection of broken stone, ballast, quartz or granite, broken to pass through 2" ring including stacking the same in standard heaps of 20'x50'x2 or 10'x50'x2' free from dust, wherever shown on prepared level ground inclusive of all charges within Railway limits. Pebbles must on no account be mixed by quarrying or by field picking. The ballast must be collected at nil points on line and on no account over cuttings more than three feet deep, or near banks over three feet high. Platforms should be got passed before starting collection. Between :— Arsikere and Habanghatta .. 20,000 C.ft. Habanghatta and Belagola ... 50,000 " Hassan and Mavinkere ... 50,000 " Mavinkere and Hole-Narsipur ... 20,000 " Hole-Narsipur and Mandagere ... 20,000 " Mandagere and Akkihebbalu ... 20,000 " Akkihebbalu and Hosa-Agrahara ... 20,000 " Hosa-Agrahara and Hampapura ... 20,000 " Yedatore and Mysore ... 30,000 "	1,000 C.ft.	2,50,000
2	Loading into and unloading from Ballast Train for leads under 20 miles.	1,000 C.ft.	2,50,000

KADUR DIVISION.

Dated 23rd July 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th August 1932, till 3 P.M. for reconstructing Ranganathaswamy Temple at Marekalhalli, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. to 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 125 (one hundred and twenty-five only), in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Reconstructing Ranganathaswamy Temple at Marekalhalli," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Percentage rates either below the estimate or lowest tender will not be accepted.

11. No claims for enhanced rates will be entertained on any account after the acceptance of tender.

12. For all lumpsum provisions detailed measurements will be taken and current scheduled rates will be allowed for items other than tendered ones.

13. The accepted tenderer is bound to execute the work as per his bond and to receive payment to the extent of grant sanctioned.

14. Any unforeseen items found necessary during execution will be paid at current scheduled rates.

15. In all matters of dispute regarding quality of the work and rates the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

Approximate quantities of estimate for reconstructing Ranganathaswamy Temple at Marekalhalli, Tarikere Taluk.

Serial No.	Items of work	Unit	Quantity	Sanctioned rate	Rate quoted	
					In figures	In words
1	Dismantling old masonry work ...	C.ft.	1,984	Rs. a. p.		
2	Do concrete over terrace (mantapa) ...	"	357	0 1 0		
3	Removing the terrace slabs without any injury to them ...	S.ft.	330	0 4 0		
4	Dismantling tiled roof over verandah including rafters, beams and posts, etc., complete ...	Sqr.	170	7 0 0		
5	Earthwork excavation for foundation ...	C.yd.	90	0 8 0		
6	Stone jelly concrete with surki mortar made in blocks of 3' x 3' x 1' ...	C.ft.	1,094	0 8 0		
7	Providing I beams 6" x 3"=12 lbs. per R.ft. ...	R.ft.	166	2 0 0		
8	Black stone in mortar ...	C.ft.	1,593	0 10 0		
9	String course 1' below cornice ...	R.ft.	112	0 6 0		
10	Cut stone work ...	C.ft.	129	3 0 0		

Serial No.	Items of work	Unit	Quantity	Estimated rate	Rate quoted	
					In figures	In words
11	Burnt stone slabs for roofing, 6" thick over garbhagudi for worship mantap including 6" projection ...	S.ft.	841	Rs. a p.	1 8 0	
12	Burnt stone slabs for bonds in foundation.	"	22	1 8 0		
13	Re-using the above slabs available ...	"	330	0 6 0		
14	Small stone jelly concrete for roofing over slabs with plastering 1 in 8 slope ...	C.ft.	363	0 9 0		
15	Nice plastering with chunam ...	Sqr.	22.73	6 8 0		
16	Teakwood battened doors 1½" thick planks with gubbi nails, bolts iron, complete with locking arrangement ...	S.ft.	46	5 0 0		
17	Teakwood windows battened double shutters ¾" iron bars hinges, tower bolts, rings, clamps, etc., complete ...	"	36	4 0 0		
18	Cuddapa slabs flooring on 3" concrete bed with cement pointing ...	Sqr.	4.26	55 0 0		
19	Earthwork below flooring and watering and tamping for 1½' depth ...	C.yd.	16	0 10 0		
20	Repairs to old steps with necessary materials ...	Lump sum		...		
21	Clearing site and levelling ground ...	Lump sum		...		
22	White washing two coats as per plastering ...	Sqr.	22.73	0 6 0		
23	Constructing entrance gopuram as per plan with masonry kalasam, images, etc., complete ...	Lump sum		...		
24	Vahanam ...	Lump sum		...		
25	Garuda image ...	No.	4	35 0 0		
26	Cornice 12" masonry ...	R.ft.	120	2 0 0		
27	Wooden railings ..	Lump sum		...		

Abstract Notification dated 16th July 1932.

Attention of the public is invited to the notification published in *Mysore Gazette*, dated 21st July 1932, page 773 of Part VI, calling for tenders for restoring Arenahalli Anicut. Last date of receiving is 3 P.M. on the 9th August 1932.

Abstract Notification dated 16th July 1932.

Attention of the public is invited to the detailed notice calling for tenders for constructing an anicut across Byranjihalla, Chikmagalur Taluk, published on pages 761 to 763, Part VI of *Mysore Gazette* of 21st July 1932.

The date of receiving tender is 8th August 1932, till 3 P.M.

Dated 23rd July 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 17th August 1932, till 3 P.M. for Re-constructing Middle School building at Sivane, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees seventy five only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Re-constructing Middle School building at Sivane, Tarikere Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Percentage rates either below the estimated or lowest tender will not be accepted.

11. No claims for enhanced rates, will be entertained on any account after the acceptance of tender.

12. For all lumpsum provisions detailed measurements will be taken and current scheduled rates will be allowed for items other than tendered ones.

13. The accepted tenderer is bound to execute the work as per his bond and to receive payment to the extent of grant sanctioned.

14. Any unforeseen items found necessary during execution will be paid at current scheduled rates.

15. In all matters of dispute regarding quality of the work and rates the decision of the Superintending Engineer, Shimoga Circle is final and legally binding.

Approximate quantities of estimate for reconstructing Middle School building at Sivane, Tarikere Taluk.

Sl. No.	Items of work	Unit	Quantity	Sanctioned rate	Rate quoted	
					In figures	In words
				Rs. a. p.		
1	Earthwork excavation ...	C.yd.	124	0 4 0		
2	Stone jelly concrete in mortar ..	C.ft.	666	0 5 0		
3	Stone in clay foundation ...	"	2240	0 5 0		
4	Stone in clay basement using old stone only.	"	853	0 2 0		
5	Burnt brick in mortar. ...	"	3,400	0 6 0		
6	Burnt stone slabs (fixing charges only) ...	S.ft.	398	0 2 6		
7	Burnt stone pillars (fixing charges only)	each	8	1 8 0		
8	Doors (fixing charges only) ...	"	6	1 8 0		
9	Windows with repairs only	"	16	1 0 0		
10	Ventilators do	"	6	1 0 0		
11	Teakwood work do	C.ft.	76.70	0 6 0		
12	Roofing with First Class Mangalore tiles on teak reepers (fixing charges only).	Sqr.	15.66	13 0 0		
13	Ridge tiles set in mortar (fixing charges only).	R.ft.	87	0 4 0		
14	Chunam plastering two coats	Sq.	53.51	5 0 0		
15	White washing two coats	"	53.51	0 5 6		
16	Flooring with Mangalore tiles on 3" concrete and cement pointing, etc.	"	9.54	36 0 0		
17	Cornice 9"	R.ft.	186	0 8 0		
18	New teakwood wall plates	C.ft.	9.56	6 0 0		
19	Compensation for lands if any	Departmental		...		
20	New materials such as to door shutters, 3 window shutters, 400 Mangalore tiles, 4 rafters, etc., including chunam borders.	Lumpsum		...		
21	Conveyance of materials from old site and clearing old site. ...	"	Do	...		
22	Clearing site and levelling ground ..	"	Do	...		

L. A. H. WINCKLER,
Executive Engineer.